

NOTES

- 1. THE BARRIER AND FOOTER SHALL BE CAST SEPARATELY USING THE FIXED FORM OR THE SLIP FORM CONSTRUCTION METHOD USING CONCRETE MIX NO.6 (4500 PSI).
- 2. THE BARRIER FOOTER AND BARRIER FORMS SHALL BE REMOVED BEFORE PLACING PAVEMENT.
- 3. WHEN THE BARRIER IS CONSTRUCTED USING THE SLIP FORM METHOD DIAGONAL NO.4 REINFORCEMENT BARS ARE REQUIRED. SEE STD. MD 648.44-04.
- 4. ALL REINFORCEMENT BARS. INCLUDING ENDS. SHALL BE EPOXY COATED. ALL BAR LAPS TO BE 30 BAR DIAMETERS. TIE BARS TOGETHER. ALL REINFORCEMENT BARS SHALL BE ASTM A 615. GRADE 60.
- 5. SPACING OF CONTRACTION JOINTS SHALL BE 20 FEET REGARDLESS OF CONSTRUCTION METHOD.
- 6. COST OF THE CONCRETE FOOTER. ALL REINFORCEMENT. AND EXCAVATION SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER LINEAR FOOT FOR 42 INCH F SHAPE CONCRETE MEDIAN TRAFFIC BARRIER BIFURCATED O INCHES TO 1 FOOT 6 INCHES.
- 7. WHEN THE BARRIER IS CONSTRUCTED ON EXISTING RIGID PAVEMENT THE COST OF ALL REINFORCEMENT. DRILLED HOLES. GROUT. LABOR. TOOLS. EQUIPMENT. ETC.. SHALL BE INCIDENTAL TO THE PRICE BID PER LINEAR FOOT FOR THE ITEM SPECIFIED IN NOTE 6.
- 8. TOLERANCES IN DIMENSIONS SHOWN SHALL BE WITHIN 1/4"

